

1.0 GENERAL

1.1 UTILITY LOCATES

The Contractor is responsible to have all underground utilities located. Contact the Utility Companies a minimum of 48 hours in advance.

2.0 MATERIALS

2.1 GARBAGE CONTAINERS:

- .1 Haul All Hid-A-Bag I standard container, 265 litres (70 gallons), single compartment, painted standard green. Containers should have access on side, not on the back of the container; no locks on doors.

2.2 BENCHES AND PICNIC TABLES

- .1 Permanent Benches – Vinyl coated bench. Blue Imp catalogue number PK 151. Colours: Standard park brown, park green or blue.
- .2 Permanent Pedestal Picnic Tables – Vinyl coated table. Blue Imp catalogue number PK-180. Colours: Standard park brown, park green or blue.

2.3 SIGNAGE

- .1 Signage to be installed as per the approved drawings. Posts for installation of signs shall be as per the approved drawings.

3.0 INSTALLATION

3.1 GARBAGE CONTAINERS

- .1 Excavate area for concrete pad. Final grade to be level with existing landscape.
- .2 Container to be mounted on poured or pre cast pad, as per manufacturer's recommendations.

3.2 BENCHES AND PICNIC TABLES

- .1 Pedestals must be set in concrete to a minimum depth of 600 mm (23.50) below finished grade.

- .2 Seating surface to be 410 - 440 mm (16 – 17.5 inches) above finished grade.
- .3 Top of concrete to be 50 mm (2 inches) below finished grade.

3.3 TRAIL SIGNS

- .1 Posts must be set in concrete to a minimum depth of 1000 mm (39.5 inches) below finished grade.
- .2 Top of concrete to be 60 mm (2 inches) below finished grade.
- .3 Signs to be installed on the posts as per the approved drawings.

4.0 SITE CLEAN UP

- .1 The Contractor shall take every precaution not to damage, injure or mark existing surfaces, structures or landscaping on the City owned property or adjacent private properties.
- .2 Any damage that may be caused by the Contractor, his employees or equipment or subcontractors, shall be restored to pre-construction condition at the Contractor's expense and to the satisfaction of the Project Manager.
- .3 All areas disturbed as a result of construction shall be reseeded as per the seeding specifications.

5.0 INSPECTION

- .1 Upon completion of installation, the contractor shall contact the Project Manager and arrange for inspection.

END OF SECTION